



NY - GEO 2025

APRIL 23-24, 2025 | SARATOGA SPRINGS, NY



2025 GeoStar Top Job Presentations

Moderator: Joanne Coons / *NY-GEO Member*

- Awardees:**
- 1) COMMERCIAL:**
 - **Ithaca Firehouse**, Wendel - Rachel Carpitella, Steve Grgas
 - 2) MIXED-USE:**
 - **Alafia**, Salas O'Brien - Peter Strupp
 - 3) MULTIFAMILY**
 - **Steamboat 20**, Aztech Geothermal - Geoff Hoffer
(an Albany Housing Authority project)



Thank you to our 2025 Top Job Judges

<u>Name</u>	<u>Info/Bio</u>	<u>Field of Work</u>
Tony Amis	Sr. Vice President, Endurant Energy	Civil Engineering, large foundations, geothermal energy piles
Eric Bosworth	Manager, Clean Technologies at Eversource Energy	Energy expert working in clean tech and utility scale geothermal networks.
Matt Dennis	Senior Home Solutions Expert, Halco Energy	Clean Energy Advisor
Jacquie Scherer	Geothermal system designer since 2005	Design and Project Management
Jim Thomas	Owner, Thomas Geothermal Engineering LLC	New Jersey licensed geothermal HVAC contractor and engineering consultant.



TOP JOBS 2025

PRESENTER (S): Rachel Carpitella

ORGANIZATION (S): Wendel

PROJECT NAME: Ithaca Fire Station

PROJECT LOCATION: Ithaca, NY




Overcoming Challenges in One of the First All-Electric Geothermal Firehouses in NYS: *A Case Study from Ithaca*

Presented by: Rachel Carpitella

April 23, 2025



Who is Wendel?



\$800M+

Energy Efficiency Projects
Since 2001

\$350M+

Annual Cost Savings
for Clients



85 yrs

in business

16

offices

300+

professionals

Lighting Improvements

Photovoltaic Systems

Site Lighting

Major HVAC Retrofits

Chiller/Boiler Plants

Geothermal

Heat Pump Systems

Ventilation system

Healthcare facilities

Laboratories

Dormitory facilities

Electric vehicle charging
stations

Retro-commissioning



wendel

Home of the Award Winning



Five Bugles
Design

+



Mitchell Associates
Architects

Over 300 programming/ feasibility studies completed
with over 150 emergency services facilities constructed!

Experienced Emergency Services Portfolio

EXPERIENCE:

20 years

ROLE / RELEVANCE:

Business Development

EXPERTISE:

Project Management
Community Engagement
Sustainability Expert
Clean Energy and Building
Decarbonization Strategy Expert



NOTEABLE ACHIEVEMENTS

Advised 100+ Large Buildings
Quadrupled Department Revenue
Secured \$15+ M in Grants/Incentives

CLIENT SECTORS

Higher Education
Healthcare
Municipal
K-12
Library
Nonprofit

PROJECT HIGHLIGHTS:

Children's Village Thermal Energy Network
Decarbonization Pre-Feasibility Tool
Advanced Codes and Standards Forum
Clean Energy Careers Job Fair

Introduction

Overview of the Ithaca Fire Station Project

- **Location:** Ithaca, NY
- **Innovative Focus:** Geothermal heat pump (GHP) firehouse in New York State built to the Ithaca Energy Code
- **Key Features:** Sustainable design, GHP system for heating, cooling, and hot water.





Ingenuity

Innovative Design Elements

- **Hybrid GHP System:** Combination of water-source Variable Refrigerant Flow (VRF) units and water-to-water heat pumps integrated with geothermal loops.
- **Enhanced Efficiency:** Energy recovery ventilation, improved zoning, and space conditioning.
- **Apparatus Room Heating:** Use of radiant floors powered by GHP for efficient heating and faster warm-up times for first responders.

Efficiency

Energy & Operational Efficiency

- **GHP System Benefits:**
 - Reduced long-term operational costs.
 - Significant decrease in greenhouse gas (GHG) emissions.
 - More efficient heating, cooling, and water heating (including radiant floors).
- **Site Efficiency:** Addressing challenges like sloping terrain and soil conditions with creative engineering solutions, ensuring minimal project delays.





Quality

High-Quality Infrastructure & Design

- **Long-Term Performance:** Integration of GHP system ensures high-quality, energy-efficient performance over time.
- **Comfort & Reliability:** Constant and controlled environment in the apparatus room, improving the comfort and effectiveness of first responders.
- **Sustainable Materials & Practices:** Designed in line with Ithaca's Green New Deal, contributing to the city's carbon-neutrality goal by 2030.

Accessibility

Community Engagement & Coordination

- **Addressing Community Concerns:** Managing noise, traffic rerouting, and maintaining good relationships with local residents.
- **Logistical Coordination:** Effective coordination of multiple stakeholders including developers, engineers, and the city.
- **Workforce Accessibility:** Compliance with prevailing wage requirements, ensuring fairness and equity for workers.





Financial

Financial Benefits & Considerations

- **Cost-Effectiveness of GHP:** Despite initial investment, the long-term operational savings and energy performance will result in significant financial benefits for the city.
- **Recovery of Lost Time:** Overcoming delays from unforeseen soil conditions led to a 75% recovery of time, optimizing financial resources.
- **Support for Ithaca's Green New Deal:** Aligning with the city's climate goals reduces future financial burdens related to energy and emissions.

Obstacles Overcome

Challenges & Problem-Solving Strategies

- **Site Challenges:** Small, sloping site with a 25-ft grade change, requiring significant earthwork.
- **Soil Conditions:** Unforeseen soil issues delayed key construction activities like sheet pile installation and GHP well placement.
 - *Solution:* Revised construction schedule and creative solution with a self-contained pump unit for slurry management, recovering 75% of lost time.
- **Coordination Challenges:** Navigating land acquisition delays, working with multiple stakeholders, and addressing logistical concerns such as noise and traffic management.
- **Weather Constraints:** Decision to focus on GHP due to dense tree cover and low winter temperatures, overcoming the feasibility challenges of solar and air-source heat pumps.



Conclusion

Key Takeaways & Future Implications

- **Innovation in Public Safety Infrastructure:** Demonstrates how GHP systems can be integrated into municipal buildings.
- **Long-Term Benefits:** Cost savings, improved efficiency, and sustainability can set a new benchmark for future projects.
- **Overcoming Obstacles:** Resilience in overcoming site, logistical, and environmental challenges ensures success in pioneering projects.





Thank you!

NY-GEO SARATOGA SPRINGS
CONFERENCE – APRIL 2025

Alafia Redevelopment Brooklyn, NY

Top Job Applicant
Mixed - Use



Project Details


- ▲ **Located in East New York/Spring Creek neighborhood of Brooklyn, NYC**
- ▲ **2,200,000 square foot mixed use development**
 - 2,400 affordable and supportive housing units, 30,000 sq ft of healthcare space, daycare facilities, fitness spaces, facilities for social and enterprises and healthy food retail space, and urban agriculture gardens.
 - 28-acre community transformation focused on wellness and economic empowerment.
- ▲ **Passive house design.** Three (3) construction phases across several buildings
 - Anticipated completion: 2030
- ▲ **Energy Assets:**
 - Geothermal (vertical closed loop) – 500' - 600' depth, 250 bores designed, 80% installed as of today.
 - Waste water (Sharc & Piranha systems) – A1/A2 & C1/C2 have Sharc, C3 has Piranha
 - Energy recovery ventilators and solar panels on roofs

Recognitions

- ▲ [L+M Development Partners](#)
- ▲ [Salas O'Brien Energy Modeling Team](#) - Bill Talbert and Marisa Dunning
 - Geothermal engineering, building energy modeling, test bore and drilling oversight
 - ConEd Clean Heat Participating Contractor and energy modeling
- ▲ [American Well & Pump](#) – Drilling and HDPE Contractor
 - [GTD-GT35](#) drill rigs, track-mounted
 - [Geo-Pro Inc](#) grouting products
 - [Oil Creek](#) & [Centennial](#) Plastics HDPE loops and piping
- ▲ [ConEd Clean Heat Program Incentives](#) - \$5.7M for 2 of 3 phases
- ▲ Architects – [Dattner](#), [Urban Architectural Initiatives](#), [Marvel](#)
- ▲ [Ice Air](#) & [Climate Master](#) – Heat Pump Equipment Providers
- ▲ [SHARC](#) & [Highmark](#) - WWHX Equipment Providers

Recognitions (continued)

- ▲ New York Geothermal Association, [NY-GEO](#)
 - 500' rule change in 2023
- ▲ United States Geological Survey, [USGS](#)
 - [Western LI Hydrogeologic Framework](#) 2024 update & [mapper](#)











Thanks!

DAN SERGISON, PE, CGD, CGI

Daniel.Sergison@salasobrien.com





Steamboat Square – Phases 1 & 2

Equitable Electrification of Public and Affordable Housing



Historic Steamboat Square

Albany Housing Authority

Since 1946, AHA has been developing and managing affordable housing in the City of Albany.


AHA currently owns and operates over 2,000 multi-family housing units for families, senior citizens and adults with disabilities.

Additionally, AHA administers a HUD Section 8 program that provides rental assistance for 2,200 households throughout the City.

Steamboat Square Homes

Originally constructed in the early 1960's.

The buildings were extensively renovated in the mid 1980's.



Steamboat Square Revitalization - Phase 1



STEAMBOAT SQUARE REVITALIZATION -PHASE 1

- 20 Rensselaer Street is the first phase in the preservation of the Steamboat Square neighborhood.
- 88 one- and two-bedroom apartments.
- **Geothermal Heat Pumps for:**
 - Heating
 - Air Conditioning
 - Domestic Hot Water – with CO2 Refrigerant Heat Pumps!
- **32 closed loop boreholes @ 499 feet deep**
 - 16 borehole under each of the two adjacent parking lots
- **Individual heat pumps for each apartment (heat/cool)**
- **Central CO2 Refrigerant Heat Pumps**
 - Higher temperature capabilities
 - Extremely low Greenhouse Warming Potential (GWP = 1)



Steamboat Square Revitalization Project Team

- **Albany Housing Authority** – Owner/Operator & Developer
- **Edgemere Development** – Development Partner
- **MR2 Construction Services** - Owner's Construction Rep
- **SWBR** – Architect **Engineered Solutions** – MEP Engineer
- **AOW Construction** – General Contractor
- **Collett Mechanical** – Mechanical Contractor
- **Claverack Pump Service** – Geothermal Driller
- **Sustainable Comfort** – Green Building Consultant
- **Aztech Geothermal** – Geothermal Consultant

SWBR


AOW
A-O-W CONSTRUCTION

Collett

Claverack
WELL & PUMP
SERVICE



**Community
Preservation
Corporation**



engineered**solutions**

Edgemere
Development Inc.
Real Estate
Development
Consulting

 **SUSTAINABLE
COMFORT**

Aztech
Geothermal

MR²
CONSTRUCTION
SERVICES



**ALBANY HOUSING
AUTHORITY**



**ALBANY HOUSING
AUTHORITY**

Phase 1

Steamboat Square Revitalization



Funding


- NYSHCR - LIHTC & Public Housing Preservation Program
- NYS Homeless Housing and Assistance Program (HHAP)
- NYSERDA/NYSHCR "Clean Energy Incentives"
- NYS Empire State Development
- NYS Attorney General Clean Energy Funds
- National Grid "Clean Heat Incentives"
- City of Albany (HOME Funding)
- Community Preservation Corporation Perm Financing (Pre-dated Federal IRA Passage for original capital stack)

Building Energy Upgrades

- All electric building design
- Ground source heat pump – Rooms and Domestic Water
- Building envelope enhancements
- ERV system
- 40% energy reduction – BTU's

Ground Heat Exchanger (GHX) Layout

- GHXs under two parking lots
- 32 x 500-foot boreholes



GENERAL NOTES:

- THIS CONTRACTOR IS RESPONSIBLE TO CALL DIG SITES AND COORDINATE WITH ALL OTHER TRACES PRIOR TO EXCAVATION OR ORDERING ANY PIPING. SOME UTILITIES HAVE BEEN NOTED ON THIS DRAWING.
- ANY CHANGES IN ELEVATION OR TO ROUTE PIPING AROUND EXISTING UTILITIES ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- PROVIDE LINK SEALS ON ALL WALL PENETRATIONS AND HORIZONTAL PIPING RUNS ARE TO BE A MINIMUM OF 4" BELOW FINAL FINISHED GRADE.
- ALL PIPING SHALL BE INSTALLED A MINIMUM OF 3" BELOW GRADE AND SHALL CONFORM TO SPECIFICATION SECTION 320.13.1.
- IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO DRILL THE WELLS AND PROVIDE ALL PIPING AND GROUT AND INSTALL THE GEOTHERMAL PIPING WITH A 6" SAND BED BELOW AND ABOVE THE PIPING. REFER TO SITE DRAWINGS FOR ALL EXCAVATION AND INFILL RESTORATION.
- ENTIRE LOOP IS TO BE FILLED WITH 20% PRE-MIXED PROPYLENE GLYCOL SOLUTION.
- CONTRACTOR IS TO COORDINATE WITH OWNER AND LOCAL AUA FOR ALL FLUSHING AND DISPOSAL OF GROUNDWATER DURING EXCAVATION AND WELL FIELD INSTALLATION.

VERIFICATION OF THE WELL LOCATIONS:

CONTRACTOR TO PROVIDE GROUND PENETRATING UNDERGROUND RADAR IN BASE OF THE PROJECT. THE RADAR SHALL BE SUBMITTED PRIOR TO THE START OF THE SITE EXCAVATION WORK. ALL SCHEDULING AND SCOPE SHALL BE COORDINATED WITH THE OWNER.

GENERAL PHASING NOTES:

- AMEND SUPPLEMENTARY CONDITIONS. IT IS ANTICIPATED THAT THE CONSTRUCTION SCHEDULE WILL ENCOMPASS TWO OR THREE VERTICAL PHASES. THE FIRST PHASE SHALL AT A MINIMUM INCLUDE THE UNOCCUPIED EAST WING PORTION OF THE TOWERS FROM FLOORS 2-12. BIDDERS MAY PROPOSE TO ALSO INCLUDE EITHER THE SOUTH OR WEST WING IN THE FIRST PHASE. THE GROUND FLOOR COMMERCIAL TENANT WILL REMAIN. ALL PROPOSED SCHEDULES AND PHASING PLANS ARE SUBJECT TO OWNER REVIEW AND APPROVAL.
- OBTAIN FULL PHASING DOCUMENTS FROM THE CONSTRUCTION MANAGER AND MAKE ALL TEMPORARY CONNECTIONS REQUIRED TO MAINTAIN HEATING AND COOLING IN OCCUPIED PORTIONS OF THE BUILDING DURING CONSTRUCTION.
- PHASING PLANS ARE SHOWN FOR GENERAL GUIDANCE AND COORDINATING PURPOSES ONLY. ALL WORK AROUND EXISTING MECHANICAL EQUIPMENT REQUIRED TO REMAIN FOR TEMPORARY PURPOSES.
- PRIOR TO REMOVING OR DISCONNECTING ANY SYSTEM COORDINATE ALL WORK WITH CONSTRUCTION MANAGER TO DETERMINE IF THE SYSTEM IS REQUIRED TO REMAIN TEMPORARILY IN ORDER TO COINCIDE WITH CONSTRUCTION PHASING AS THE PROJECT PROGRESSES.
- PROVIDE ANY CUTTING & PATCHING OF EXISTING FLOORS/WALLS AS REQUIRED.
- IF THE NEW PIPING IS INSTALLED IN AN ALTERNATE LOCATION FOR PHASING PURPOSES ITS RELOCATION TO REQUIRED FINAL LOCATION IS REQUIRED TO BE COMPLETED.
- CONTRACTOR TO VERIFY PNEUMATIC LINES FEEDING BUILDINGS. EXISTING LINES ARE TO REMAIN UNTIL THE ENTIRE BUILDING IS TURNED OVER AND COMPLETELY OPERATIONAL ON THE NEW GEOTHERMAL PLANT. PROVIDE ANY NEW PNEUMATIC LINES AS REQUIRED WHERE EXTENSION OF EXISTING LINES IS NOT APPLICABLE.
- CONTRACTOR TO REMOVE AND RE-INSTALL ANY CEILING DUCTS/GEOSOLAR AS REQUIRED FOR ARCHITECTURAL WORK TO TAKE PLACE. THIS INCLUDES TAKING DOWN ANY OFFICE GEOSOLAR FOR ANY ROUNDOFF OF MECHANICAL WORK OR PIPING WHETHER SHOWN ON ARCHITECTURAL CEILING PLANS OR NOT.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE OWNER FOR THE INSTALLATION OF THE NEW GEOTHERMAL PLANT DESIGNED TO FEED THE EXISTING RENOVATED 13 STORY STEAM-BOILER BUILDING. THE GEOTHERMAL PIPING AND PLANT HAS INTENDED TO BE PLACED AND PIPED PRIOR TO THE REMOVAL OF THE EXISTING BOILER PLANT IN THE BASEMENT MECHANICAL SPACE.

Thermal Conductivity Report - 5/12/2022

Project Name: Steamboat Square Phase 1
Project Address: 21 Albany Street
Client: SWBR
Date: 5/12/2022
By: FVC
Project Manager: FVC/K

Subsurface Report

Well	Depth (ft)	Temperature (°F)	Flow Rate (GPM)
Well #1	100	58.0	1.0
Well #2	100	58.0	1.0
Well #3	100	58.0	1.0
Well #4	100	58.0	1.0
Well #5	100	58.0	1.0
Well #6	100	58.0	1.0
Well #7	100	58.0	1.0
Well #8	100	58.0	1.0
Well #9	100	58.0	1.0
Well #10	100	58.0	1.0
Well #11	100	58.0	1.0
Well #12	100	58.0	1.0
Well #13	100	58.0	1.0
Well #14	100	58.0	1.0
Well #15	100	58.0	1.0
Well #16	100	58.0	1.0
Well #17	100	58.0	1.0
Well #18	100	58.0	1.0
Well #19	100	58.0	1.0
Well #20	100	58.0	1.0
Well #21	100	58.0	1.0
Well #22	100	58.0	1.0
Well #23	100	58.0	1.0
Well #24	100	58.0	1.0
Well #25	100	58.0	1.0
Well #26	100	58.0	1.0
Well #27	100	58.0	1.0
Well #28	100	58.0	1.0
Well #29	100	58.0	1.0
Well #30	100	58.0	1.0
Well #31	100	58.0	1.0
Well #32	100	58.0	1.0

Flow Rate Report Parameters

Well	Flow Rate (GPM)	Temperature (°F)
Well #1	1.0	58.0
Well #2	1.0	58.0
Well #3	1.0	58.0
Well #4	1.0	58.0
Well #5	1.0	58.0
Well #6	1.0	58.0
Well #7	1.0	58.0
Well #8	1.0	58.0
Well #9	1.0	58.0
Well #10	1.0	58.0
Well #11	1.0	58.0
Well #12	1.0	58.0
Well #13	1.0	58.0
Well #14	1.0	58.0
Well #15	1.0	58.0
Well #16	1.0	58.0
Well #17	1.0	58.0
Well #18	1.0	58.0
Well #19	1.0	58.0
Well #20	1.0	58.0
Well #21	1.0	58.0
Well #22	1.0	58.0
Well #23	1.0	58.0
Well #24	1.0	58.0
Well #25	1.0	58.0
Well #26	1.0	58.0
Well #27	1.0	58.0
Well #28	1.0	58.0
Well #29	1.0	58.0
Well #30	1.0	58.0
Well #31	1.0	58.0
Well #32	1.0	58.0

Notes

- 1. 10" CPVC wellhead
- 2. 10" CPVC wellhead
- 3. 10" CPVC wellhead
- 4. 10" CPVC wellhead
- 5. 10" CPVC wellhead
- 6. 10" CPVC wellhead
- 7. 10" CPVC wellhead
- 8. 10" CPVC wellhead
- 9. 10" CPVC wellhead
- 10. 10" CPVC wellhead
- 11. 10" CPVC wellhead
- 12. 10" CPVC wellhead
- 13. 10" CPVC wellhead
- 14. 10" CPVC wellhead
- 15. 10" CPVC wellhead
- 16. 10" CPVC wellhead
- 17. 10" CPVC wellhead
- 18. 10" CPVC wellhead
- 19. 10" CPVC wellhead
- 20. 10" CPVC wellhead
- 21. 10" CPVC wellhead
- 22. 10" CPVC wellhead
- 23. 10" CPVC wellhead
- 24. 10" CPVC wellhead
- 25. 10" CPVC wellhead
- 26. 10" CPVC wellhead
- 27. 10" CPVC wellhead
- 28. 10" CPVC wellhead
- 29. 10" CPVC wellhead
- 30. 10" CPVC wellhead
- 31. 10" CPVC wellhead
- 32. 10" CPVC wellhead

SWBR

200 West Street, Suite 1200
Albany, NY 12202
Phone: (518) 262-2410
Fax: (518) 262-2411
www.swbr.com

engineered solutions

444 West River Road
Albany, NY 12202
Phone: (518) 262-2410
Fax: (518) 262-2411
www.esdynamics.com

AS-BUILT 3.26.24

HCR SHARS NO. - 20210448

Drawn By: FVC
Checked By: FVC
Project Manager: FVC/K

Revisions

Rev	Date	Description
1	05/18/22	Addendum #3
2	05/11/23	AS-BUILT

Steamboat Square Revitalization - Phase 1

SWBR Project Number: 21122.00

Albany Housing Authority

M-101

GEOTHERMAL WELL FIELD LAYOUT


7/26/22
Construction Documents

Ground Heat Exchanger (GHX) Layout

- GHXs under two parking lots
- 32 x 500-foot boreholes

16 x 500' Vertical Boreholes

16 x 500' Vertical Boreholes



200 West Street, Suite 100
Albany, NY 12202
Phone: (518) 262-4100
Fax: (518) 262-4441
www.swbr.com
EPC/EST

engineered solutions

444 West Street, Suite 100
Albany, NY 12202
Phone: (518) 262-4100
Fax: (518) 262-4441
www.engineered.com
EPC/EST

AS-BUILT 3.26.24

HCR SHARS NO. - 20210448

Drawn By: FVC
Checked By: FVC
Project Manager: FVC/K

These documents and all the data, information, drawings and plans are the property of the company and shall not be used for any other purpose without the written consent of the company. The company shall not be responsible for any errors or omissions in these documents.

Revisions


Rev	Date	Description
1	05/18/22	Addendum #3
2	05/11/23	ASB 014

Steamboat Square Revitalization - Phase 1
SWBR Project Number: 21122-00

Albany Housing Authority

M-101
GEOTHERMAL WELL FIELD LAYOUT
7/26/22
Construction Documents

GEOTHERMAL PIPING SCHEMATIC




- DRAWING NOTES:**
- REFER TO MANIFOLD DIAGRAMS ON M-704 FOR ADDITIONAL INFORMATION AND DIMENSIONAL REQUIREMENTS
 - PROVIDE NEW CONCRETE PAD IN EXISTING PIT WHERE ABANDONED STEAM CONDENSATE RECEIVER IS TO BE REMOVED. PIPING AND MANIFOLDS ARE TO BE INSTALLED ON METAL GRATING SYSTEM SUSPENDED ABOVE LOWEST POINT OF MECHANICAL ROOM PIT.

- GENERAL NOTES:**
- PROVIDE BALL VALVE OR WAFFER VALVE FOR ALL BRANCH PIPING GREATER THAN 2". A SHUT OFF VALVE IS TO BE PROVIDED FOR EACH PIECE OF EQUIPMENT AND AT EVERY BRANCH PIPE THROUGHOUT THE PROJECT.
 - ALL PIPING TO BE WELDED WITHIN THE EAST AND WEST SHAFTS AS WELL AS FROM THE DECKER MECHANICAL TUNNEL TO THE NEW TOWER BASEMENT CEILING LEVEL REGARDLESS OF WHICH ALTERNATE IS TAKEN.
 - IT IS THE CONTRACTOR'S RESPONSIBILITY TO FLUSH ALL PIPING AS MANY TIMES REQUIRED TO COORDINATE WITH ALL PHASING PLANS. THIS MAY REQUIRE FLUSHING OVER NIGHT FOR MULTIPLE DAYS AT A TIME TO KEEP THE DECKER BUILDING OPERATING.
 - IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE A WATER SAMPLE AND ANALYSIS PRIOR TO PURCHASING ANY HYDRONIC EQUIPMENT AND PROVIDING A WATER TREATMENT AND FILTRATION RECOMMENDATION FROM A CERTIFIED WATER TREATMENT SPECIALIST. THE SPECIALIST'S RECOMMENDATION FOR WATER QUALITY MUST BE INCLUDED IN THE CONTRACTOR'S SCOPE OF WORK AND TO BE SIGNED OFF BY CHILLER, COOLING TOWER, BOILER MANUFACTURER'S PRIOR TO ORDERING.
 - IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ACCESS TO VALVES, AND PIPING SPECIALTIES TO BE SERVED BY FACILITY IN THE FUTURE. THIS CONTRACTOR IS RESPONSIBLE FOR PROVIDING ACCESS DOORS AT EACH LEVEL OF THE SHAFT AND FOR FUTURE ACCESS.
 - CONTRACTOR TO PROVIDE PRE-MIX PROPYLENE GLYCOL FOR ALL LOOPS CALLED OUT TO HAVE GLYCOL ON PLANS. THE CONTRACTOR SHALL INCLUDE VOLUME FOR ALL TANKS, EQUIPMENT, PIPING AND ADDITIONAL TO FILL THE GLYCOL INJECTION TANKS.
 - CONTRACTOR IS RESPONSIBLE FOR CONNECTING TO ANY EXISTING PIPING REQUIRED FOR RE-CONNECTION REGARDLESS OF THE CONDITION OF THE PIPE. THIS MAY REQUIRE SPECIAL SCHEDULING WITH OWNER AND IN SOME CASES HOT TAPPING ANY LIVE PIPING.
 - CONTRACTOR IS TO FLUSH ANY EXISTING AND OR NEW PIPING AS MANY TIMES AS REQUIRED UNTIL ALL PHASING IS COMPLETE. IN SOME CASES THIS MAY INCLUDE MULTIPLE FLUSHINGS FOR A SINGLE GIVEN AREA BASED ON THE FINAL PHASING PLAN ACCEPTED BY THE OWNER.
 - THE CONTRACTOR SHALL INCLUDE SHUT OFF VALVES FOR ALL BRANCH PIPING AND TAKE-OFFS. ALL MAINS SHALL HAVE SHUT-OFFS AT EACH EXIT POINT OF MECHANICAL ROOM, SHAFT AND PENTHOUSE.
 - CONTRACTOR TO NOTE CHILLED WATER AND HOT WATER GLYCOL PERCENTAGES FOR EACH PIPING LOOP. GLYCOL PERCENTAGES WILL VARY DEPENDING ON THE APPLICATION.
 - PROVIDE NEW SHUT OFF VALVES ON EACH FLOOR OF STEAMBOAT BUILDING FOR PHASING AND FUTURE MAINTENANCE PURPOSES.

Heat Pump Riser Diagram

- Source water from GHX to 88 units + common space HPs
- No isolation – same water running through vertical GHXs




AS-BUILT 6.24.24

GeoFease Loop Monitoring

- Monitoring Ground Loop Temp and Flow Rate
- System compares to original design
 - Flags Trends



GeoFease Loop Monitoring





Geothermal Drilling & Looping





Excavation for Geothermal Piping



Geothermal Circuit Header Piping Trench

(under parking lot)


Geothermal Pipes Entering Building – Valves Inside





Pressure Testing

Heat Pump Selections for Building



Omega Vertical Stack Heat Pumps
Ducted supply – Central Return



Installed Vertical Stack in Apartment

CO2 Refrigerant Domestic Hot Water Heat Pump & Storage Tanks



Domestic Hot Water Storage Tanks




Lync CO2 Heat Pumps for Domestic Hot Water

Steamboat Square Project Phases

Albany Housing Authority's Steamboat Square projects are all going geothermal. It will be ~425 affordable housing units when it's finished in mid 2026.

Phase I is underway - a 88 unit/12 story tower @ 20 Rensselaer St.

(one townhouse not pictured)



**Steamboat
Phase 1**


**Steamboat
Phase 2**

Phase 2

Steamboat Square Revitalization



- **Additional 332 apartments and 6 commercial spaces**
- **Featuring Geothermal Network (Campus Style):**
 - **Heating**
 - **Air Conditioning**
 - **Domestic Hot Water – with CO2 Refrigerant Heat Pumps!**
- **Phase 2 will access IRA Tax Credits for:**
 - **Geothermal Heat Pumps**
 - **Possibly Solar PV with Battery Storage**



Thank You & Questions



NY - GEO 2025

APRIL 23-24, 2025 | SARATOGA SPRINGS, NY



2025 GeoStar Top Job Presentations

Moderator: Joanne Coons / *NY-GEO Member*

Awardees: 1) **COMMERCIAL:**

- **Ithaca Firehouse**, Wendel - Rachel Carpitella, Steve Grgas

2) **MIXED-USE:**

- **Alafia**, Salas O'Brien - Peter Strupp

3) **MULTIFAMILY**

- **Steamboat 20**, Aztech Geothermal - Geoff Hoffer
(an Albany Housing Authority project)